Tiny Detachable Premade Mobile Homes Checkpoint Temp Control Station

Basic Information

• Place of Origin: China

Brand Name: INFINITE STARS

• Certification: CE, ISO14001, ISO9001, ISO45001

Model Number: D09Minimum Order Quantity: 7 Sets

Price: USD 1200~1500/Set
Packaging Details: 7 units/20gp 17 units/40hq
Supply Ability: 2000 Sets PER Month



Product Specification

• Application: Checkpoint, Temp Control Station

Column And Beam: Bolted

• Electricity Device: Swich,light,soket,etc

Main Structure: Galvanized Light Steel Frames

Material: Steel

• Standard Size: 5950*3000*2800

Structure: Galvanlized Steel FrameColor: White Or Customized Color

Main Material: Light Steel Frame & Sandwich Panel

Wall Material: Rock Wool Sandwich Panel

• MOQ: 7 PCS

• Highlight: Detachable Premade Mobile Homes,

Tiny Premade Mobile Homes, ISO9001 Premade Mobile Homes



Product Description

Premade Tiny Detachable Container House Checkpoint Temp Control Station

The detachable container house, when utilized as a checkpoint or temporary control station, exhibits several key features. Its modular design allows for rapid setup and disassembly, enabling swift deployment and relocation. Structural stability is maintained despite their detachable nature, ensuring durability and reliability. Thermal insulation and fire-resistant materials such as EPS fireproof sandwich panels provide excellent insulation and safety. Customizability allows for tailored dimensions, materials, and functions to meet specific needs. Wide applicability spans checkpoints, control stations, and various temporary facilities. In summary, the detachable container house offers speed, mobility, stability, safety, customization, versatility, and support as an ideal solution for checkpoints and temporary control stations.

| Standard Quic | k Assembly Cor | ntainer House Datasheet |
|---|---------------------|--|
| Product Specification: 3-meter standard container | Length(mm) | 5950(5730) |
| | Width(mm) | 3000(2800) |
| | Height(mm) | 2800(2500) |
| | Center column | |
| | Roof | Flat roof, free drainage |
| | Number of floors | ≤3 |
| Design parameters | Service life | 5-8 years |
| | Ground live load | 1.8KN/ |
| | Roof live load | 0.5KN/ |
| | Wind load | 0.6KN/ |
| | Seismic degree | 8 |
| Structural | corner column | galvanized cold rolled section steel, t=2.3mm, material Q235B |
| | roof main beam | galvanized cold rolled section steel, t=2.3mm, material Q235B |
| | | Galvanized square steel 5*5, t=1.5mm, radian galvanized square steel 4*6t= 1.2mm material Q235B |
| | floor main beam | galvanized cold-rolled section steel, t=2.3mm, material Q235B |
| | floor sub- beam | galvanized square steel 4*8 (5), galvanized square steel 8*8 (4) material Q235B |
| | Paint | Graphene Powder spraying (Electrostatic spraying) |
| Roof | Roof panel | 0.40mm thick color steel plate, color white gray |
| | Ceiling | 0.25mm thick 811 ceiling, color white gray |
| Floor | Decorative surface | |
| | basic floor | 18mm sanding board |
| | Thickness | 50mm thick color steel glass fiber sandwich board; The outer and inner plates are made of 0.3mm aluminum plated zinc color steel plate |
| | | |

| | Heat preservation | 50mm thick glass silk wool, bulk weight ≥60kg/m³, combustion performance is class A non-combustible |
|-------------|----------------------|--|
| | Color | white gray PE coating |
| Door | Spec(mm) | Width X height =920*2030 common door |
| Door | Material | Steel door |
| Window | Spec(mm) | Front window: width X height =920*1200; Rear window (standard) : width X height =920*1200; |
| | Frame | Plastic steel window single glass |
| | Glass | common |
| | Voltage | 220V~250V |
| Electricity | Wire | input power wire is 4 square, AC wire is 4 square, socket wire is 2.5 square, lighting switch wire is 1.5 square |
| Liouriony | Circuit breaker | High break Miniature Circuit breaker (32A) |
| | Lamp tube | Two sets of circular LED fluorescent lamps |
| | Socket | 3 five-hole socket 10A, 1 three-hole air conditioning socket 16A |

As a wholly-owned subsidiary of Wujiang Saima (established in 2005), Suzhou Stars Integrated Housing Co., Ltd. focuses on foreign trade. As one of the most professional prefabricated house manufacturers in south-east China, we provide customers with all kinds of integrated housing solutions.

Equipped with complete production lines, including sandwich panel production machines and steel structure production line, with 5000 square meter workshop and professional staff, we already built long-term business with domestic giants like CSCEC and CREC. Also, based on our export experience in the past years, we are furthering our steps to global customers with best product and service.

As a supplier to overseas customers all over the world, we are very familiar with the manufacturing standards of various countries, such as European standards, American standards, Australian standards, and so on. We have also participated in the construction of many large-scale projects, such as recent 2022 Qatar World Cup camping construction. Suzhou Stars Integrated Housing Co., Ltd. mainly has five types of products: folding container house, flat pack container house, detachable container house, modified shipping container (in development), and steel structure construction, which can be widely used in many fields, such as dormitory, camp, office, canteen, shop, toilet and shower, viewing pavilion, firefighting station, isolation ward, etc.







Suzhou Stars Integrated Housing Co., Ltd.

+8615228076365

sales@szstarshouse.com



prefabricated-containerhouses.com

NO.1 ZHUJIABANG VILLIAGE.ZHENZE TOWN,WUJANG,SUZHOU,CHINA