



Jiangsu Portable Container House Manufacturer | Customizable Designs

Our Product Introduction

for more products please visit us on prefabricated-containerhouses.com

Basic Information

- Place of Origin: china
- Brand Name: INFINITE STARS
- Certification: CE,ISO9001,ISO45001,ISO14001
- Minimum Order Quantity: 7 Sets
- Payment Terms: L/C,D/A,D/P,T/T,Western Union,MoneyGram
- Supply Ability: 2000 Sets PER Month



Product Specification

- Quick-Assembly Design: Modular Components Enable Rapid On-site Installation Without Heavy Machinery
- Robust Steel Structure: Fully Welded Steel Frame Ensures High Strength, Durability, And Superior Seismic/anti-deformation Performance
- Thermal & Acoustic Insulation: Walls Constructed With Color Steel Sandwich Panels Provide Effective Heat Preservation, Soundproofing, And Weather Resistance
- Weatherproof & Corrosion-Resistant: Treated Materials Withstand Harsh Environments (humidity, Acid, Alkali, Salt Fog) For Long-term Use
- Multi-Functional Applications: Ideal For Site Offices, Guard Booths, Living Quarters, Modular Hotels, Schools, And Emergency Housing



More Images



Product Description

Fast Assembly Container House - Premium Prefabricated Solution

Features & Advantages

Rapid Installation

Modular design enables on-site assembly within hours, reducing labor costs by 60% compared to traditional buildings. Interlocking steel frames require no welding, ensuring seamless connections and structural stability.

Durability & Safety

High-grade galvanized steel structure (wall thickness: 0.15-0.2mm) withstands harsh weather and seismic activity. Fire-retardant PU foam insulation (70-80kg/m³ density) maintains indoor temperatures (-20°C to 40°C).

Customization Flexibility

Stackable up to 3 floors with reinforced corner castings (ISO standard). Configurable as offices, dormitories, or guard booths; optional add-ons include AC ports, windows, and partition walls.

Eco-Friendly Design

100% reusable materials and reduced construction waste align with green building standards.

Technical Parameters

Item	Specification
Dimensions (L×W×H)	6058×2438×2896 mm

more products please visit us on prefabricated-containerhouses.com

Item	Specification
Wall Panel	50mm composite sandwich
Roof Load	150 kg/m²
Lifespan	15+ years
Delivery Time	7-15 days (MOQ: 5 units)

FAQ Section

Q1: How long does installation take?

A single unit installs in 2-3 hours with basic tools.

Q2: Can you customize sizes?

Yes, tailor-made sizes (e.g., 12m×3m) available for bulk orders.

Q3: Is it suitable for coastal areas?

Anti-corrosion spray coating protects against saltwater erosion.

Q4: What logistics support do you offer?

FOB Shanghai/Ningbo ports; global shipping with on-site assembly guidance.

Why Choose Us?

As a **Suzhou-based manufacturer** with 10+ years' expertise, we provide end-to-end solutions from design to installation. Our ISO-certified production facility (20,000m²) ensures strict quality control. Partner with us for cost-efficient, scalable modular buildings that redefine rapid deployment.



Suzhou Stars Integrated Housing Co., Ltd.



+8615228076365



sales@szstarhouse.com



prefabricated-containerhouses.com

NO.1 ZHUJIABANG VILLIAGE.ZHENZE TOWN,WUJANG,SUZHOU,CHINA